

BANGALORE DIVISION.

Abstract Notification dated 8th January 1938.

The attention of the public is hereby invited to the detailed notification inviting tenders for the construction of buildings for the fruit orchard at Hesserghatta, Bangalore Taluk, published on pages 48-55 of Part VI of the *Mysore Gazette*, dated 13th January 1938. The last date for receipt of the tender is 2 P.M. on 2nd February 1938 and the earnest money to accompany the tender is Rs. 1,160.

Notification dated 19th January 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 14th February 1938, for restoring Hettaki Kodagikere, Reg. No. 265 of Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 190 (one hundred and ninety) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Hettaki Kodagikere, Reg. No. 265 of Hoskote Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond after depositing an additional sum of Rs. 190, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for restoring Hettaki Kodagikere Tank, Register No. 265 of Hoskote Taluk.

No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Rate	Quantity	Figures	Words
			Rs. a. p.			
	<i>Bund.</i>					
1	Clearing jungle with roots	Grade	3 0 0	11		
2	Cutting steps and grips	"	1 8 0	11		
3	Earthwork to bund with the required lead and lift including consolidation	C.yd.	0 4 0	6,500		
4	Turfing the slopes of bund and watering till it is satisfactory	S.yd.	0 0 10	3,625		

No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Rate	Quantity	Figures	Words
			Rs. a. p.			
5	Rough stone pitching 9" thick with the required lead lift and jelly packing, etc., complete ..	S.yd.	0 4 0	883		
6	New stone revetment with the required lead lift jelly backing and jelly edging, etc., complete ..	C.yd.	1 12 0	200		
7	Removing and resetting old stone work with the required new jelly backing and jelly wedging, etc., complete ..	"	0 12 0	189		
8	Gravel backing to revetment with the required lead, lift and consolidation ..	"	0 9 6	67		
9	Providing and fixing new grade stones including lead slabs, cutting figures and painting complete ..	Each	2 8 0	11		
10	Do B. M. stones do ..	"	3 0 0	2		
11	Do Register No. and date stone do ..	"	3 0 0	1		
12	Do Gauge stone do ..	"	12 0 0	1		
13	Do Index stones do ..	"	0 8 0	11		
<i>Pipe Shuice..</i>						
1	Earthwork cut opening the bund and refilling with consolidation ..	C.yd.	0 5 0	80		
2	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 3 6	160		
3	Burnt brick in surki mortar ..	"	0 4 6	600		
4	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar ..	S.ft.	0 6 0	16		
5	Surki mortar plastering ..	Sqr.	4 0 0	2.00		
6	Providing and fixing plug iron rod with locking arrangements, etc., complete ..	Each	15 0 0	1		
7	Making holes in orifice slab ..	"	0 8 0	4		
8	Carting the required pipe supplied departmentally at Bangalore, laying, fixing with cement joints, etc., complete. ..	R.ft.	..	30		
<i>Waste Weir R.L. 51.50. Length 80 ft.</i>						
1	Earthwork draft and approach clearing and using the same to the bund with consolidation ..	C.yd.	0 4 0	110		
2	Burnt stone jelly in surki concrete ..	C.ft.	0 3 3	253		
3	Burnt brick in surki mortar ..	"	0 4 6	500		
4	Surki mortar plastering ..	Sqr.	4 0 0	5.00		
5	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar ..	S.ft.	0 6 0	340		
6	Removing the rough stone work old in the bund and resetting with the required new jelly and jelly wedging, etc., complete ..	C.yd.	0 12 0	76		

Notification dated 21st January 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 14th February 1938, for constructing one and a half block of Line Men's Quarters at Kaglipur, Kankanhalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and ninety only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing one and a half block of Line Men's Quarters at Kaglipur, Kankanhalli Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, after depositing an additional sum of Rs. 190, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department, or those fixed by the Executive Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than the estimated rate will not be accepted.

Approximate quantities required for constructing one block of Line Men's Quarters at Kaglipur, Kankanhalli Taluk (one and a half block is proposed to be constructed.)

Items of work	Unit	Sanctioned		Rate quoted in	
		Quantity	Rate	Figures	Words
			Rs. a. p.	Rs. a. p.	Rs.
1. Earthwork excavation and filling in basement	C.yd.	33	0 4 0		
2. Stone jelly concrete in lime mortar	C.ft.	387	0 3 7		
3. Burnt size stone in clay for foundation and basement face hammer dressed with bond stones at every 6 ft. in each layer	"	1,002	0 4 0		
4. Burnt bricks in clay superstructure	"	1,831	0 3 6		
5. Burnt brick in mortar for sides of doors, windows and top of walls	"	427	0 4 3		
6. Burnt stone slabs one line dressed and fixed in mortar	S.ft.	140	0 4 0		
7. Binding wall 6"×6" with burnt brick in lime mortar, chunam plastering, whitewash, etc., complete	R.ft.	30	0 5 0		
8. Chunam plastering, two coats $\frac{3}{4}$ " thick	Sqr.	4,536	3 0 0		

Items of work	Unit	Sanctioned		Rate quoted in	
		Quantity	Rate	Figures	Words
			Rs. a. p.	Rs. a. p.	Rs.
9. Pointing with chunam mortar and thread lines	Sqr.	1.45	1 8 0		
10. White and colour washing, two coats.	"	46.81	0 5 0		
11. Roofing with 1st class Mangalore tiles on teakwood batten 2"×1" with wood oiling to reepers including nailing and fixing the eave tiles by a teak batten screwed down to the rafters and painted with chocolate.	"	13.18	24 0 0		
12. Providing and fixing ridge tiles in mortar and pointed with cement	R.ft.	68	0 7 6		
13. Providing and fixing ventilating tiles in mortar and pointed with cement.	Each	16	1 8 0		
14. Honneywood work wrought and put-up with two coats of wood oiling	C.ft.	51.81	3 12 0		
15. Teakwood door frames 4"×3" in section with 1½" thick Honneywood battened shutters with iron clamps, fittings, wooden cleats, etc., complete	S.ft.	156	1 6 0		
16. Windows with 4"×3" in section, teakwood frames and 1½" thick Honneywood battened shutters ¾" diameter, iron bars, iron clamps and fittings, etc., complete	"	60	1 12 0		
17. Providing and fixing stone pestle and mortar	Each set.	4	6 0 0		
18. Flooring with burnt stone jelly in lime mortar 3" thick and over it 1½" thick cement concrete and plastered with cement ½" thick mixed with red ochre and cut into squares and finished complete	Sqr.	8.03	18 0 0		
19. Silicate painting, two coats	"	5.28	3 0 0		
20. Wall shelves with 3"×4" teakwood frame, 1" thick Honneywood cross planks and Honneywood battened shutters 1½" thick with iron clamps and fittings, etc., complete	S.ft.	48	1 2 0		
21. Expanded metal frame work 2½"×2" in section teakwood frames and doorways including painting two coats with silicate painting, etc., complete.	"	246	0 12 0		

N. LAKSHMINARASIMHAIA,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 24th January 1938.

Attention of the public is drawn to the Notification calling for tenders for Maintenance Work to Tumkur Amanikere, Register No. 1, Tumkur Taluk, in pages 86-87, Part VI in the *Mysore Gazette*, dated 20th January 1938.

Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 8th February 1938.

An earnest money of Rs. 300 in cash should accompany the tender.